# This Page Is Inserted by IFW Operations and is not a part of the Official Record

## **BEST AVAILABLE IMAGES**

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images may include (but are not limited to):

- BLACK BORDERS
- TEXT CUT OFF AT TOP, BOTTOM OR SIDES
- FADED TEXT
- ILLEGIBLE TEXT
- SKEWED/SLANTED IMAGES
- COLORED PHOTOS
- BLACK OR VERY BLACK AND WHITE DARK PHOTOS
- GRAY SCALE DOCUMENTS

## IMAGES ARE BEST AVAILABLE COPY.

As rescanning documents will not correct images, please do not report the images to the Image Problem Mailbox.

### **PCT**

WORLD INTELLECTUAL PROPERTY ORGANIZATION Inicanational Bureau

## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 5:

(11) International Publication Number:

WO 91/04088

B01D 24/02

A1

(43) International Publication Date:

4 April 1991 (04.04.91)

(21) International Application Number:

PCT/US90/05141

(22) International Filing Date:

11 September 1990 (11.09.90)

(30) Priority data: 405,977

12 September 1989 (12.09.89) US

(71) Applicant: PALL CORPORATION [US/US]; 30 Sea Cliff Avenue, Glen Cove, NY 11542 (US).

(72) Inventors: PALL, David, B.; 5 Hickory Hill, Roslyn Estates, NY 11576 (US). GSELL, Thomas, C.; 40 Valentine Avenue, Glen Cove, NY 11542 (US). MUELLERS, Brian, T.; 112 Driscoll Avenue, Rockville Centre, NY 11570 (US).

(74) Agent: FOSTER, John, D.; Leydig, Voit & Mayer, 700
Thirteenth Street, Northwest, Suite 300, Washington, DC 20005 (US).

(81) Designated States: AT (European patent), AU, BE (European patent), CH (European patent), DE (European patent)\*, DK (European patent), ES (European patent), FR (European patent), GB (European patent), IT (European patent), JP, KR, LU (European patent), NL (European patent), SE (European patent).


**Published** 

With international search report. Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.

(54) Title: DEVICE AND METHOD FOR PROCESSING BLOOD FOR HUMAN TRANSFUSION

#### (57) Abstract

A device for processing donated blood comprises a porous medium interposed between the collection bag (11) and a satellite bag (13) into which a component separation by centrifugation can be expressed, the filter element preferably having a CWST of about 70 to about 115 dynes/cm. The porous medium blocks red blood cells, but allows platelets to pass therethrough.



#### **DESIGNATIONS OF "DE"**

Until further notice, any designation of "DE" in any international application whose international filing date is prior to October 3, 1990, shall have effect in the territory of the Federal Republic of Germany with the exception of the territory of the former German Democratic Republic.

#### FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AT	Austria	RS	Spain	MC	Monaco
AU	Australia	FL	Finland	MG	Madagascar
BB	Barbados	FR	France	ML	Mali
BE	Belgium	GA	Gabon	MR	Mauritania
BF	Burkina Fasso	GB	United Kingdom	MW	Malawi
BG	Bulgaria	GR	Greece	NL	Notherlands
BJ	Benin	HU	Hungary	NO	Norway
BR	Brazil	IT	İtaly	PL	Poland
CA	Canada	JP	Japan	RO	Romania
CF	Central African Republic	KP	Democratic People's Republic	SD	Sudan
CG	Canen		of Korea	SE	Sweden
CH	Switzerland	KR	Republic of Korca	SN	Senegal
CM	Cameroon	Li	Liechtenstein	SU	Soviet Union
DB	Ссгталу	LK	Sri Lanka	TD	Chad
DK	Denmark	LU	Luxembourg	TC	Togo
			-	us	United States of America

## DEVICE AND METHOD FOR PROCESSING BLOOD FOR HUMAN TRANSFUSION

This application is a continuation-in-part of U.S. Serial No. 07/405,977, filed September 12, 1989.

#### Technical Field:

This invention relates to a method for processing blood donated for the purpose of therapeutic transfusion of blood components and, particularly, to improved means for preparing, from the donated whole blood, leucocyte depleted platelet concentrate (hereinafter PC), packed red cells (hereinafter PRC), and plasma.

#### 15 Background Art:

20

25

The development of plastic blood collection bags facilitated the separation of donated whole blood into its various components, thereby making platelet concentrates available as a transfusion product. The separation of a single unit of donated whole blood, about 450 milliliter in USA practice, into its components is typically accomplished by use of differential sedimentation.

A typical procedure used in the United States, the citrate-phosphate-dextrose-adenine (CPDA-1) system, utilizes a series of steps to separate donated blood into three components, each component having substantial therapeutic and monetary value. The procedure typically utilizes a blood collection bag

10

to which is integrally attached at least one, and preferably two, satellite bags. Whole blood may be thus collected and processed as follows:

- (1) The donated whole blood is collected from the donor's vein directly into the blood collection bag which contains the nutrient and anti-coagulant containing CPDA-1.
- (2) The blood collection bag is centrifuged together with its satellite bags, thereby concentrating the red cells as packed red cells (PRC) in the lower portion of the blood collection bag and leaving in the upper portion of the bag a suspension of platelets in clear plasma, which is known as platelet-rich plasma (PRP).
- 15 (3) The blood collection bag is transferred, with care not to disturb the interface between the supernatant PRP layer and the sedimented PRC layer, into a device known as a "plasma extractor" which comprises an opaque back plate and a transparent front plate; the two plates are hinged together at their lower ends and spring biased toward each other such that a pressure of about 200 to 300 millimeters of mercury is developed within the bag.

With the blood collection bag positioned between the two plates, a valve is opened allowing the 25 supernatant PRP to flow into a first satellite bag. As the PRP flows out of the blood collection bag, the interface with the PRC rises. The operator closely observes the position of the interface as it 30 rises and clamps off the connecting tube when in his judgment as much PRP has been transferred as is possible, consistent with allowing no red cells to enter the first satellite bag. This is a time consuming operation during which the operator must 35 visually monitor the bag and judiciously and

10

25

30

35

arbitrarily ascertain when to shut-off the connecting tube. The blood collection bag, now containing only PRC, is then detached and stored at 4°C until required for transfusion into a patient.

- (4) The PRP-containing satellite bag, together with the second satellite bag, is then removed from the extractor and centrifuged at an elevated G force with the time and speed adjusted so as to concentrate the platelets into the lower portion of the PRP bag. When centrifugation is complete, the PRP bag contains platelet concentrate in its lower portion and clear plasma in its upper portion.
- extractor, and the clear plasma is expressed into

  the second satellite bag, leaving the first bag containing only PC. Again, the operator must judiciously and arbitrarily ascertain when to halt plasma flow into the second bag. The PRP bag, now containing PC, is then detached and stored for up to

  five days at 20°-22°C until needed for a transfusion of platelets. For use with adult patients, the platelets from 6-10 donors are, when required, pooled into a single platelet transfusion.
  - (6) The plasma in the second satellite bag is usually separated by complex processes into a variety of valuable products.

Commonly used systems, other than CPDA-1, include Adsol and SAG-M. In these systems, nutrient solution is preplaced in the second nutrient bag, and this solution is transferred into the PRC in an additional step after the PRP has been separated from the PRC, thereby achieving a higher yield of plasma and longer storage life for the PRC.

The separation of blood into components has substantial therapeutic and monetary value. This is

nowhere more evident than in treating the increased damage to a patient's immune system caused by the higher doses and stronger drugs now used during chemotherapy for cancer patients. These more aggressive chemotherapy protocols are directly implicated in the reduction of the platelet content of the blood to abnormally low levels; associated internal and external bleeding additionally requires more frequent transfusions of PC, and this has caused platelets to be nationally in short supply and has put pressure on the blood banks to increase platelet yield per unit of blood.

Blood bank personnel have responded to this pressure by attempting to increase PC yield in a variety of ways, including attempting to express 15 more PRP prior to stopping flow from the blood collection bag. This has often proved to be counterproductive in that the PRP, and the PC subsequently extracted from it, were not infrequently contaminated by red cells, giving a pink or red color 20 to the normally light yellow PC. The presence of red cells in PC is so highly undesirable that pink or red PC is frequently discarded, or subjected to recentrifugation, both of which increase operating 25 costs.

The devices and methods of this invention alleviate the above-described problems and, in addition, provide a higher yield of superior quality PC.

10

15

20

25

30

5

## Leucocyte Depletion of Platelet Suspensions

The transfusion of platelet concentrate which has not been leuco-depleted is not without risk for those patients receiving both acute and chronic transfusion support. Chills, fever, and allergic reactions may occur in patients receiving acute as well as chronic platelet therapy. Repeated platelet transfusions frequently lead to alloimmunization against HLA antigens, as well as platelet specific antigens. This, in turn, decreases responsiveness to platelet transfusion. Leucocytes contaminating platelet concentrates, including granulocytes and lymphocytes, are associated with both febrile reactions and alloimmunization, leading to platelet transfusion refractoriness. Another life-threatening phenomenon affecting heavily immunosuppressed patients is Graft Versus Host Disease. clinical syndrome, donor lymphocytes transfused with the platelet preparations can launch an immunological reaction against the transfusion recipient with pathological consequences.

Growing evidence suggests that the use of leucocyte depleted platelet concentrates decreases the incidence of febrile reactions and platelet refractoriness. Leucocyte depleted blood components are also believed to have a role in reducing the potential for Graft Versus Host Disease. Leucocyte depletion of platelet preparations are also believed to diminish, but not to completely prevent, the transmission of leucocyte associated viruses such as HIV-1 and CMV.

Platelet preparations contain varying amounts

15

20

25

30

35

of leucocytes. Platelet concentrates prepared by the differential centrifugation of blood components will have varying leucocyte contamination related to the time of centrifugation and G force used. While the dose of contaminating leucocytes necessary to cause a febrile reaction or to elicit platelet refractoriness in repeated transfusion remains unknown, several recent studies report a reduction of alloimmunization and platelet refractoriness at levels of leucocyte contamination  $< 1 \times 10^7$  per unit. These and other studies suggest that at least a two log (99%) reduction of leucocyte contamination is required. More recent studies suggest that a three log (99.9%) or four log (99.99%) reduction would be significantly more beneficial.

U. S. Patent 4,880,548 (hereinafter '548) provides a convenient and very effective means of leuco-depletion of PC. PC is passed through a fibrous filter which permits recovery of 90% or more of the platelets, which pass through the filter, while retaining within the filter more than 99.9% of the incident leucocytes. This system is currently in widespread use at bedside in hospitals, but, unlike the device of this invention, it is not well suited for use in blood banks during the processing of donated blood. The unsuitability stems primarily from additional storage constraints associated with PC and the methods of administering PC. For example, platelets in PC are typically suspended in a total volume of only about 40 to 60 ml of plasma. Contrasted with this, the platelets which are processed by the devices and methods of this invention are derived from a single unit of whole blood and are suspended as PRP in about 180 to 240 ml of plas-Further, the platelets in PC have been

10

15

20

25

30

subjected during centrifugation to severe conditions and there is reason to believe that, as a result of the high forces to which the platelets are subjected as they reach the bottom of the bag during sedimentation, they are not as readily dispersed, i.e., they are more aggregated by particle-to-particle adhesion, when compared with the platelet distribution in PRP.

For these and perhaps other reasons, platelets in PC show a much higher tendency to be retained within the filter during leuco-depletion compared with platelets in PRP. Indeed, one of the advantages of the devices and methods of this invention is that much better recovery is obtained when platelets are leuco-depleted in the form of PRP, compared with PC; for example, while optimal recovery from PC is about 90 to 95%, recovery from PRP can exceed 99%.

Also, as a consequence of the concentration differences and possibly as a consequence of the lower degree of aggregation in PRP, the preferred critical wetting surface tension (CWST) range when filtering PRP is broader than those for PC.

#### Brief Description of the Drawings:

Figure 1 is a representational view of a typical blood collection set for the collection and processing of blood. The set 10 comprises a collection bag 11 with flexible tubing 12 connected thereto and leading to a first satellite bag 13 (for PRP) and a second satellite bag 15 (for plasma) connected to the first satellite bag 13 via flexible tubing 16.

Figure 2 is identical to Figure 1 except that tubing 12 has been cut and filter 14 inserted.

10

15

20

25

30

#### Disclosure of the Invention:

PC is typically prepared from donated blood that has been stored until needed and transfused to the patient at bedside as required. Insofar as leuco-depletion of platelets derived from donated blood has been practiced, it has generally been accomplished just prior to or contemporaneous with the transfusion to the patient.

In the methods of this invention, leucocyte depletion is accomplished at the time the blood is processed, which in USA practice is within 8 hours of the time the blood was drawn. Step number three of the six step process of blood bank practice presented in a preceding section is modified by interposing a leucocyte depletion filter 14 immediately downstream of the blood collection bag 11 (see Figure 2). Thus, as the supernatant PRP is expressed by the plasma extractor, leucocytes are removed by the filter and leucocyte-depleted PRP is collected in the satellite bag and is subsequently centrifuged to obtain leucocyte-depleted PC and plasma.

In a preferred form of the filter of the subject invention, the fibers of which the filter element is composed are modified by grafting thereon a mixture of two monomers, one containing hydroxyl groups and another containing anionic groups, such as carboxyl groups, with the hydroxyl groups present in larger numbers. As described in U. S. Patent 4,880,548, herein incorporated by reference, the filter media of this invention are preferably surface modified using a mixture comprising hydroxylterminated and carboxyl-terminated monomers. In a

15

20

25

30

35

preferred form of this invention, the monomers are respectively hydroxyethyl methacrylate and methacrylic acid, and the monomer ratios are preferably in the range (carboxyl:hydroxyl) of .01:1 to 0.5:1, and more preferably in the range of .05:1 to 0.35:1. A preferred monomer ratio is one which produces a desired zeta potential at the pH of plasma (7.3) of -3 to -30 millivolts, a more preferred ratio produces a zeta potential of -7 to -20 millivolts, and a still more preferred ratio produces a zeta potential of -10 to -14 millivolts.

The CWST of the filter elements made with the PBT fibers according to this invention have a CWST as formed of about 50 to 54 dynes/cm, and most or all other fibers which may be used have a CWST below 55 dynes/cm. Surface grafting using the monomers noted above causes the CWST of the fibers to increase, the exact value obtained being dependent on the ratio of the two monomers. A preferred range for the CWST of the devices of this invention is about 70 to 115 dynes/cm, a more preferred range is 90 to 100 dynes/cm and a still more preferred range is 93 to 97 dynes/cm, these ranges being obtained by varying the ratio of carboxyl-terminated and hydroxyl-terminated monomers.

Although the fibers of the porous medium may remain untreated, they are preferably treated to make them even more effective. For example, the fibers may be surface modified to increase the critical wetting surface tension (CWST) of the fibers.

As disclosed in U.S. Patent No. 4,880,548, the CWST of a porous medium may be determined by individually applying to its surface a series of liquids with surface tensions varying by 2 to 4

10

20

25

30

35

dynes/cm and observing the absorption or nonabsorption of each liquid over time. The CWST of a
porous medium, in units of dynes/cm, is defined as
the mean value of the surface tension of the liquid
which is absorbed and that of the liquid of
neighboring surface tension which is not absorbed
within a predetermined amount of time. The absorbed
and non-absorbed values depend principally on the
surface characteristics of the material from which
the porous medium is made and secondarily on the
pore size characteristics of the porous medium.

Liquids with surface tensions lower than the CWST of a porous medium will spontaneously wet the medium on contact and, if the medium has through holes, will flow through it readily. Liquids with surface tensions higher than the CWST of the porous medium may not flow at all at low differential pressures and may do so unevenly at sufficiently high differential pressures to force the liquid through the porous medium. In order to achieve adequate priming of a fibrous medium with a liquid such as blood, the fibrous medium preferably has a CWST in the range of about 53 dynes/cm or higher.

The number of carboxyl groups per unit of surface area appears to have an important effect on the adhesion of platelets to fiber surfaces. This effect is reflected in the proportion of platelets recovered in the filter effluent as a fraction of the number present in the platelets prior to filtration. Platelet recovery peaks at the optimum proportion of methacrylic acid (MAA). The number of carboxyl groups per unit of fiber surface is, over the range of interest of this invention, thought to be close to proportional to the amount of MAA in the monomeric grafting solution.

25

30

i f 'i

The porous medium of this invention may be formed, for example, from any synthetic polymer capable of forming fibers and of serving as a substrate for grafting. Preferably, the polymer should be capable of reacting with at least one ethy-5 lenically unsaturated monomer under the influence of ionizing radiation without the matrix being adversely affected by the radiation. Suitable polymers for use as the substrate include, but are not limited to, polyolefins, polyesters, polyamides, polysul-10 fones, acrylics, polyacrylonitriles, polyaramides, polyarylene oxides and sulfides, and polymers and copolymers made from halogenated olefins and unsaturated nitriles. Examples include, but are not limited to, polyvinylidene fluoride, polyethylene, 15 polypropylene, cellulose acetate, and Nylon 6 and 66. Preferred polymers are polyolefins, polyesters, and polyamides. The most preferred polymer is polybutylene terephthalate (PBT).

surface characteristics of a fiber can be modified by a number of methods, for example, by chemical reaction including wet or dry oxidation, by coating the surface by depositing a polymer thereon, and by grafting reactions which are activated by exposure to an energy source such as heat, a Van der Graff generator, ultraviolet light, or to various other forms of radiation. The preferred method is a grafting reaction using gamma-radiation, for example, from a cobalt source.

Radiation grafting, when carried out under appropriate conditions, has the advantage of considerable flexibility in the choice of reactants, surfaces, and in the methods for activating the required reaction. Gamma-radiation grafting is particularly preferable because the products are very

10

15

stable and have undetectably low aqueous extractable levels. Furthermore, the ability to prepare synthetic organic fibrous media having a CWST within a desired range is more readily accomplished using a gamma radiation grafting technique.

An exemplary radiation grafting technique employs at least one of a variety of monomers each comprising an ethylene or acrylic moiety and a second group, which can be selected from hydrophilic groups (e.g., -COOH, or -OH). Grafting of the fibrous medium may also be accomplished by compounds containing an ethylenically unsaturated group, such as an acrylic moiety, combined with a hydroxyl group, such as, hydroxyethyl methacrylate (HEMA), acrylic acid, or combined with methacrylic acid. Use of HEMA as the monomer contributes to a very high CWST. Analogues with similar functional characteristics may also be used to modify the surface characteristics of fibers.

In a first variation of the devices of this in-20 vention, the PRP derived from a single unit of about 450cc of human blood is passed, typically during a flow interval of about 10 to 40 minutes, through a filter comprising the grafted fibers, the element of the filter preferably comprising fibers with a 25 surface area in the range of about 0.15 to 1.0 square meters, and more preferably about 0.2 to 0.7 square meters, with a voids volume in the range of 78% to 89% (i.e., if PBT fiber is used, corresponding to a density of the filter element in 30 the range of 0.15 g/cc to 0.30 g/cc), and more preferably 81% to 85% (for PBT, 0.21 g/cc to 0.26 g/cc). The filter element is preferably of right cylindrical form with the ratio of diameter to thickness preferably in the range of about 7:1 to 35

10

15

20

25

35

about 40:1. The range of fiber diameter is preferred to be about 1.0 to  $4\mu m$  and is more preferred to be in the range of about 2 to  $3\mu m$ . These parameters can be varied; for example, the diameter of the filter element could be reduced and the thickness of the filter element increased while retaining the same total quantity of fiber, or the fibers could be larger in diameter while increasing the total quantity of fiber, or the fibers could be packed as opposed to preformed into a cylindrical disc. Such variations fall within the purview of this invention.

If desired, flow rate of the PRP through the filter can be regulated to obtain a total flow period of about 10 to 40 minutes by selecting the appropriate element diameter, element thickness, fiber diameter, and density, and/or by varying the diameter of tube 12 either upstream or downstream of the filter, or both up and downstream. At these flow rates, leucocyte depletion efficiency in excess of about 99.9% may be achieved and even as high as 99.995%. These levels of efficiency result in a PC product with substantially less than 10<sup>7</sup> leucocytes per unit of PC (a unit of PC is the volume of PC obtained from a single unit of donated blood).

The above-described device and its mode of use provide the advantages set forth below, among other advantages.

- (a) In the blood bank, the filtration step

  requires no labor input additional to the current practice, and, in the hospital, the need for bedside filtration is completely eliminated.
  - (b) The volume of the PRP processed is about five or more times that of the PC which is derived from the PRP. Because the volume processed is

10

15

35

larger, loss of PC due to hold up within the filter is only about 1% compared with a loss about five or more times greater when PC is filtered at bedside.

- (c) Compared with hospital practice, filtration within the blood bank is generally under better control, as it is performed in relatively larger numbers by personnel trained to the specific task.
- (d) It is the belief of some researchers that when PC is stored prior to removal of leucocytes, the platelets are damaged during storage as the leucocytes disintegrate, releasing their components, some of which are highly toxic to human tissues. Removing the leucocytes within a few hours after collection is believed to greatly reduce damage due to this cause.
- (e) In the process of tapping the donor's vein, the hypodermic needle cuts a disc of the donor's skin which is transferred into the collected blood. The alcohol swab applied prior to venipunc-20 ture is not adequate to assure sterility of this skin disc. Thus, the skin disc may contain one or more varieties of bacteria, the most common being Staphylococcus epidermidis, which has been detected in PC along with other organisms. The presence of 25 the skin disc in PC is a suspect source of bacterial growth during storage, and it is fear of such growth which is the principal impetus for the regulation (in the USA) which limits the storage life of platelets to five days. Removal of the skin disc by filtration at an early stage of processing is, for this 30 reason, an important advantage as it may permit the five day regulation to be relaxed.
  - (f) Compared with a bedside filtration method of '548, improved recovery of platelets is obtained, i.e., recovery in excess of 98% to 99% compared with

10

15

20

25

30

35

about 90 to 95% typically recovered in bedside filtration.

In a second variation of this invention, the interposed filter 14 is preferably made with smaller fiber surface area, smaller filter element flow area, higher filter element density, and reduced voids volume in relation to the first variation. The total quantity of fiber used is also reduced such that a preferred range for the fiber surface area of the filter element is .04 to .3  ${
m M}^2$  and a more preferred range is .06 to .20 M<sup>2</sup>. A preferred range for the filter element flow area is 3 to 8 cm2, and a more preferred range is 4 to 6 cm2. A preferred range for the relative voids volume is about 71% to about 83% (corresponding for PBT fibers to a density of .23 to .40 g/cc), and a more preferred range is from 73% to 80% (.27 to .37 g/cc). A preferred range for the CWST of the fiber is 70 to 115 dynes/cm, a more preferred range is 90 to 100 dynes/cm, and a still more preferred range is 93 to 97 dynes/cm. Because of its very small size, a preferred device in accordance with the second variation of the invention retains internally only 0.5 to 1 cc of PRP, representing less than a 0.5% loss of platelets.

Filters made in accordance with this second variation and which are interposed between the blood collection bag and PRP bag will generally remove about 85 to 99% or more of the incident leucocytes. Table II shows that this removal rate is not sufficient to consistently achieve a residual leucocyte count of less than 10<sup>7</sup> leucocytes per 50 ml of PC. A principal function of this device, however, is to act as an automatic "valve" during the decantation process by instantly stopping the flow of PRP at the

moment that red cells contact the filter surface. The mechanism of this valve-like action is not well understood, but it may reflect aggregation of the red cells as they reach the filter surface, forming a barrier which prevents or blocks further flow of PRP through the filter element. Aggregation of red cells on contact with the filter surface appears to be related to the CWST and/or to the surface characteristics of the fibers which are generated by the herein described procedure for modifying the 10 fibers. This theory for the proposed mechanism is supported by the existence of filters capable of highly efficient leucocyte depletion of human red blood cell suspensions and which have pore sizes as 15 small as  $0.5\mu m$ . In these filters, red cells pass freely and completely through the filters with no clogging, with applied pressure of the same magnitude as that used in the present invention. the other hand, filters of the present invention, which typically have pore diameters larger than 20 about 0.5 mm, abruptly stop the flow of red blood cells when the filter is contacted by the red cells. This suggests that the filter's valve-like action is not related to or caused by pore size or by a filtration mechanism. The mechanism of this valve-25 like action is not well understood, but it may reflect zeta potential-related aggregation of the red cells as they reach the filter surface, forming a barrier which prevents or blocks further flow of PRP through the filter element. 30

The advantages to be gained by the use of this device include the following:

- (a) The collected PRP, and the PC derived therefrom, are substantially free of red cells.
- 35 (b) The operator needs only to start the flow

10

15

of PRP, which will continue to flow into the first satellite bag until red cells contact the filter surface, at which point flow stops. This eliminates the need for a skilled operator to estimate when to stop flow. The PRP so obtained has the faintly yellow color of normal PRP and, for practical purposes, may be considered to be free of red cells. The PC derived from the PRP has the characteristic light yellow color of PC and, for practical purposes, may be considered to be essentially free of red cells.

- (c) The volume of PRP recovered from the blood collection bag during the plasma extraction operation is increased by about 2% to about 3% when compared with very competent manual operation and probably by about 2% to about 5% compared with average blood bank practice.
- (d) Labor input is reduced, as monitoring of the interface during decantation is not required.
- (e) Freshly donated blood contains platelets varying in age from newly formed to nine days or 20 more (platelet half-life in vivo is about nine days). Newly formed platelets are larger and are generally believed to be more active. Because the younger platelets are larger, they tend to sediment faster during centrifugation and, consequently, are 25 present in larger numbers in the PRP nearest to the red cell interface. Measurements have shown that the concentration of platelets in the 10% of the PRP volume nearest the interface is about twice that in the uppermost 10% of PRP. Taking this into account, 30 the total number of platelets recovered is increased by about 4 to 10%.

10

15

20

25

30

Incremental number
 of platelets, %

2 to 5

Due to increased volume
of PRP
Due to the higher
concentration of

platelets in the incremental volume

of PRP 2 to 5

Total 4 to 10%

Total 4 to 10%

- (f) The larger proportion of younger platelets in the PC administered to the patient means that their life within the patient after administration will be longer and that the platelets will be more active, compared with current blood bank practice.
- (g) The yield of plasma, a component of value comparable with that of PRC and PC, is also increased by about 2 to about 5%.
- (h) Insofar as the plasma yield is increased, the plasma content of the PRC is decreased. This is advantageous because the MHC (major histocompatibility complex) contained in the plasma is responsible for the occurrence of Urticaria (hives) in a proportion of transfusion recipients transfused with PRC.

In a third variation of this invention, the fiber is surface modified as for the preceding versions, but the fiber surface area of the element is increased while, at the same time, the density of the filter element is somewhat reduced. In this way, all of the advantages of the preceding variations are provided together with higher efficiency of leucocyte depletion.

30

A preferred range of fiber surface area for the third variation of the invention is from 0.3 to 2.0M<sup>2</sup>, and a more preferred range is from 0.35 to 0.6M2. The upper limits of fiber surface area reflect the desire to accomplish the filtration in a 5 relatively short time period, and may be increased if longer filtration times are acceptable. A preferred voids volume of a filter for a filter element is in the range of 71% to 83% (i.e., if PBT fiber is used, corresponding to a density of the fi-10 lter element in the range of 0.24 g/cc to 0.40 g/cc), and more preferably 75% to 80% (for PBT, 0.28 g/cc to 0.35 g/cc). A preferred filter element flow area is from about 2.5 to 10 cm2, and a more preferred area is from about 3 to 6 cm2. Leucocyte 15 depletion efficiencies in excess of about 99.9 to 99.99%, which corresponds to an average residual leucocyte content per unit of less than about .005 x 10<sup>7</sup>, can be obtained.

#### 20 <u>Conversion of density when</u> using fibers other than PBT

In the preceding exposition the term density has been used, and the density values quoted for the filter element have been based on the use of PBT fibers. Other fibers which differ in density from the PBT may be used, as noted above, providing that their surfaces have, or have been modified to have, the characteristics noted above, e.g., a CWST of greater than 70 dynes/cm. In accordance with the invention, to use an alternate fiber of different density, the density of an element made using an alternate fiber may be calculated as follows:

10

15

Denoting V as a percentage of the voids volume relative to the apparent volume of the PBT element [i.e., V = (volume of voids/volume of element) x 100], the objective is to calculate the element density of an alternate fiber element which will have a relative voids volume percentage equal to V.

If F is the density of the alternate fiber and 1.38 g/cc is taken as the density of PBT fiber, and M<sub>1</sub> is the element density of the PBT element and M<sub>2</sub> is the density required for an element with equivalent performance, then voids volume V of the PBT fiber element is

 $V = (1 - M_1/1.38) \times 100$ 

and the density required for the element made using the alternate fiber is

$$M_2 = F (1 - V/100)$$
.

The more preferred fiber diameter range for the practice of this invention is about 2 to 3  $\mu$ m, the diameter being defined in terms of surface area, as described in U. S. Patent 4,880,548. This range is preferred because much above this range, the dimensions of the elements and consequently the liquid

10

15

hold-up volumes of the filters become significantly larger; below this range, the filter elements become relatively less coherent and are more easily compressed. For example, an element made using less than 2  $\mu$ m polypropylene fibers would be compressed by the pressure developed by the plasma extractor, which can be as high as 300 mm of Hg.

Pore diameters of filter elements in accordance with the invention can be determined using the modified OSU F2 method as described in U. S. Patent 4,925,572.

In accordance with the invention, a useful technique for the measurement of fiber surface area, for example by nitrogen gas adsorption, is that developed by Brunauer, Emmet, and Teller in the 1930's, often referred to as the "BET" measurement. Using PBT as an example, the surface area of melt blown webs can be used to calculate average fiber diameter:

Total volume of fiber in 1 gram =  $\frac{1}{1.38}$  cc (where 1.38 = fiber density of PBT, g/cc)

hence 
$$\frac{\pi d^2 L}{4} = \frac{1}{1.38}$$
 (1)

25 Area of the fiber is  $\pi dL = A_f$  (2)

Dividing (1) by (2), 
$$\frac{d}{4} = \frac{1}{1.38A_f}$$

and 
$$d = \frac{4}{1.38A_f} = \frac{2.9}{A_f}$$
, or  $(0.345A_f)^{-1}$ 

where L = total length of fiber per gram, d = average fiber diameter in centimeters, and  $A_f$  = fiber surface area in cm<sup>2</sup>/g. If the units of d are

micrometers, the units of  $A_f$  become  $M^2/g$  (square meters/gram), which will be used hereinafter. For fibers other than PBT, substitute the density for 1.38.

<u>Examples</u>

Each of the examples was run using the following basic procedure to process and test a bag of donated blood. The blood collection set was constituted as shown in Figure 1. Bag 11, into which anticoagulant had been placed, was used to 10 collect one unit of about 450cc of blood from a human volunteer. Bag 11 along with its two satellite bags was then centrifuged for 5 minutes at 2280 X gravity, causing the red cells to sediment into the lower parts of the bag and leave a transparent, 15 yellowish layer of red cell-free plasma in the upper part of the bag. This bag was then transferred, with care not to disturb its contents, to a plasma extractor. With tube 12 clamped adjacent to bag 11 to prevent flow, tube 12 was cut and the test filter 20 was inserted at position 14 in Figure 2. With the plasma extractor applying sufficient force to the bag to generate a pressure of about 200 to 300 millimeters of mercury within the bag, the clamp on tube 12 was removed, allowing the supernatant liquid 25 to flow through the filter into bag 13 which had been placed on a weight scale. One of several skilled operators was instructed to signal when, in normal blood bank practice, flow would have been manually shut off. For examples 1 and 2, which were 30 in accordance with the first variation of this invention, tube 12 was at the signal promptly shutoff, the weight of PRP collected was recorded, and

10

15

the contents of the bag analyzed, with results recorded in Table I.

For examples 3-8 and 9-10, the weight of the PRP bag 13 was recorded at the signal, i.e., the precise moment when flow would in normal blood bank practice have been shut off, while flow was allowed to continue until the red cell layer reached filter 14, at which time flow spontaneously and abruptly stopped, and the weight of PRP collected was recorded. The results for examples 3-8 are shown in Table II, and for examples 9 and 10 in Table III.

In each of the ten examples, the resulting PRP was visually free of red cells, and weights of the PRP were converted to volume by dividing by the density of plasma (1.04 g/cc). The data on residual leucocyte content of the PC derived from the filtered PRP are reported in Tables II and III as multiples of 10<sup>7</sup> (i.e., X 10<sup>7</sup>), which can be conveniently compared with a target criterion of fewer than about 1 X 10<sup>7</sup> leucocytes per unit, which is a level believed adequate to significantly reduce alloimmunization in patients receiving platelet transfusions.

The widely used melt blowing process for making fibrous plastic webs is a convenient, economical, and effective means for manufacturing fibrous webs with fiber diameter in the 1 - 4μm range. It is characteristic of this process that the quality of melt blown webs is optimal when the web weight is maintained in a preferred range of about .0005 to about .01 g/cm², and more preferably between .0005 and about .007 g/cm². For this reason, the webs used to form the examples of this invention were, wherever necessary, formed by laying up two or more layers of web of weight about .006 g/cm², and then

hot compressing these to form an integral filter element.

#### Examples 1-2

Devices were prepared in the manner of the first variation of this invention. The filter 5 elements of these devices were preformed from 2.6  $\mu \mathrm{m}$ average diameter PBT fibers, which had been surface modified in the manner as described above and as taught in U.S. Patent 4,880,548 using a mixture of hydroxyethyl methacrylate and methacrylic acid in a 10 monomer ratio of .35:1 to obtain a CWST of 95 dynes/cm and a zeta potential of -11.4 millivolts. Filter element effective diameter was 4.74 cm, presenting a filter area of 17.6 cm<sup>2</sup>, thickness was 0.15 cm, voids volume was 83% (density = 0.23 g/cc), 15 and fiber surface area was 0.69 M2. The volume of PRP held up within the filter housing was 2.5 cc, representing a loss of PRP due to hold-up of about The results, obtained using the operating procedure described earlier in this section for the 20 first variation, are shown in Table I.

TABLE I

Leucocyte Depletion Efficiency of the First Variation

25	Example <u>Number</u>	Volume of PRP passed,	Leucocyte content of PC after filtration (per unit)*	Leucocyte removal efficiency,**
	1	237	<.006 x 10 <sup>7</sup>	>99.9%
30	2	206	$<.006 \times 10^{7}$	>99.9%

\*Total leucocyte count in the PC after centrifuging the filtered PRP to obtain the PC.

\*\* Assumes that the leucocyte content of the PRP prior to filtration conformed to an average value of 5 x 10<sup>7</sup> per unit.

10

15

20

25

#### Examples 3-8

Devices were prepared in the manner of the second ("automatic valve") variation of this invention. The filter elements of these devices were preformed from 2.6µm average diameter PBT fibers, which had been surface modified in the manner as described above and as taught in U. S. Patent 4,880,548 using hydroxyethyl methacrylate and methacrylic acid in a monomer ratio of .35:1 to obtain a CWST of 95 dynes/cm and a zeta potential of -11.4 millivolts. The filter element's effective diameter was 2.31 cm, presenting a filter area of 4.2 cm², thickness was .051 cm, voids volume was 75% (density, 0.34 g/cc), and fiber surface area was .08m².

The volume of PRP held up within the filter housing was <0.4 cc, representing a loss of PRP due to hold-up of less than 0.2%. In each test, flow stopped abruptly as red cells reached the upstream surface of the filter element, and there was no visible evidence of red cells or hemoglobin downstream. The results obtained, using the operating procedure described earlier in this section for the second variation, are shown in Table II.

#### TABLE II

	1	2	3	4	5
5		Estimated volume/PRP	Volume of PRP obtained using the	Incre-	Leuco- cyte content after filtrat- ion (per
10	Example Number	using normal blood bank practice, ml	procedure of invention, ml	mental volume, percent	unit) of PC* x 10 <sup>7</sup>
	<u> </u>	pruocroc, mr	CICIL, MI	Dercent	<u>x 10 </u>
	3	175.2	178.8	2.0	1.0
	4	212.9	218.8	2.7	1.7
	5	221.1	225.7	2.0	0.5
15	6	185.9	191.4	2.9	0.2
	7	257.2	263.2	2.3	<0.1
	8	196.6	200.7	2.1	0.1

<sup>\*</sup> Total leucocyte count in the PC after centrifuging the filtered PRP to obtain PC.

#### 20 Examples 9-10

Devices were prepared in the manner of the third variation of this invention, i.e., the combination of an automatic shut-off valve and a high efficiency filter, both comprised in a single filter. The filter elements of these devices were 25 preformed from 2.6 mm average diameter PBT fibers, which had been surface modified in the manner as described above and as taught in U.S. Patent 4,880,548 using a mixture of hydroxyethyl methacry-30 late and methacrylic acid in a monomer ratio of .35:1 to obtain a CWST of 95 dynes/cm and a zeta potential of -11.4 millivolts at the pH of plasma The filter element effective diameter was 2.31 cm presenting a filter area of 4.2 cm<sup>2</sup> thickness 35 was 0.305 cm, density was 0.31 g/cc (voids volume = 77.5%), and fiber surface area was  $0.46 \text{ M}^2$ .

10

volume of PRP held up within the filter housing was 1.3 cc, representing a loss of PRP due to hold up within the filter of about 0.5%. In each case, flow stopped abruptly as red cells reached the upstream surface of the filter element, and there was no visible evidence of red cells or hemoglobin downstream. The results obtained, using the operating procedure described earlier in this section for the third variation, are shown in Table III.

#### TABLE III

## Incremental Volume and Leucocyte Depletion Efficiency of the Third Variation

15			Volume		Leuco- cyte content	
20	Example Number	Estimated volume/PRP using normal blood bank practice, ml	of PRP obtained using the procedure of inven- tion, ml	Incre- mental volume,	after filtrat- ion (per unit) of PC* x 10 <sup>7</sup>	Leuco- cyte remov- al effi- ciency**
	9	251	256	2	<.004	>99.9\$
	10	212	216	1.9	.005	>99.9%

<sup>25 \*</sup> Total leucocyte count in the PC after centrifuging the filtered PRP to obtain PC.

<sup>\*\*</sup> Assumes that the leucocyte content of the PRP prior to filtration conformed to an average value of 5 x  $10^7$  per unit.

#### Claims:

- 1. A device for the collection and processing of blood comprising a first container and at least one second container connected thereto, wherein a
- 5 leucocyte filter is interposed between the first container and the second container, the leucocyte filter permitting platelet-rich plasma to pass therethrough, and wherein the leucocyte filter has a CWST of at least 70 dynes/cm.
- 10 2. The device of claim 1 wherein the first container is a blood collection bag and the second container is a satellite bag.
  - 3. The device of claim 1 wherein the CWST is from 70 dynes/cm to 115 dynes/cm.
- 15 4. The device of claim 1 wherein the fibers of the filter have been modified by exposure to a monomer comprising a polymerizable group and a hydroxyl-containing group.
- The device of claim 4 wherein the monomer is
   hydroxyethyl methacrylate.
  - 6. The device of claim 1 wherein the fibers of the filter have been modified to present hydroxyl groups and carboxyl groups.
- 7. The device of claim 6 wherein the fibers of the filter have been modified with a mixture of monomers comprising hydroxyethyl methacrylate and methacrylic acid.

- 8. The device of claim 7 wherein the acid/acrylate monomer weight ratio in the modifying mixture is between .01:1 to 0.5:1.
- 9. The device of claim 1 wherein the surface area of the fibers of the leucocyte filter is 0.15 to 1.0  $\text{M}^2$ .
  - 10. The device of claim 9 wherein the leucocyte filter has a voids volume of 78% to 89%.
- 11. The device of claim 1 in which the zeta 10 potential is -3 to -30 millivolts at pH of 7.3.
  - 12. The device of claim 11 in which the zeta potential is -7 to -20 millivolts at pH of 7.3.
  - 13. The device of claim 12 in which the zeta potential is -10 to -14 millivolts at of pH 3.
- 15 14. The device of claim 6 in which the zeta potential is -7 to -20 millivolts at pH of 7.3.
  - 15. The device of claim 1 wherein the leucocyte filter comprises polybutylene terephthalate fibers.
- 16. The device of claim 7 wherein the fibers20 comprise polybutylene terephthalate.
  - 17. A device for the collection and processing of blood comprising a first container and at least one second container connected thereto, wherein a filter barring passage of red blood cells is interposed between the first container and the second container,

サナレ シェナ びそひひび

5

the filter permitting platelets to pass therethrough, but blocking red blood cells.

- 18. The device of claim 17 wherein the fibers of the filter have been modified to present hydroxyl groups and carboxyl groups.
  - 19. The device of claim 18 wherein the fibers of the filter have been modified with a mixture of monomers comprising hydroxyethyl methacrylate and methacrylic acid.
- 10 20. The device of claim 19 wherein the acid/acrylate monomer weight ratio in the modifying mixture is between .01:1 to 0.5:1.
  - 21. The device of claim 20 wherein the ratio is .05:1 to .35:1.
- 15 22. The device of claim 20 wherein the CWST is 70 dynes/cm to 115 dynes/cm.
  - 23. The device of claim 22 wherein the CWST is from 90 dynes/cm to 100 dynes/cm.
- 24. The device of claim 23 wherein the CWST is from 20 93 dynes/cm to 97 dynes/cm.
  - 25. The device of claim 17 wherein fibers in the filter have a surface area of 0.04 to .30  $\text{M}^2$ .
  - 26. The device of claim 25 wherein the surface area is .06 to .2  $M^2$ .

- 27. The device of claim 25 wherein the filter has a voids volume of 71% to 83%.
- 28. The device of claim 27 wherein the voids volume is 73% to 80%.
- 5 29. The device of claim 17 wherein the flow area of the filter is 3-8 cm<sup>2</sup>.
  - 30. The device of claim 29 wherein the flow area is  $4-6 \text{ cm}^2$ .
- 31. The device of claim 17 wherein the zeta
  10 potential of the fibrous structure is -3 to -20
  millivolts at pH of 7.3.
  - 32. The device of claim 31 in which the zeta potential is -3 to -30 millivolts at pH of 7.3.
- 33. The device of claim 32 in which the zeta 15 potential is -7 to -20 millivolts at pH of 7.3.
  - 34. The device of claim 17 wherein the leucocyte filter comprises polybutylene terephthalate fibers.
  - 35. The device of claim 22 wherein the fibers comprise polybutylene terephthalate.
- 20 36. The device of claim 17 wherein the hold-up volume is less than 1cc.
  - 37. The device of claim 17 wherein the first container is a blood collection bag and the second container is a satellite bag.

sage of platelets.

- 38. A device for the collection and processing of blood comprising a blood collection bag and at least one satellite bag connected thereto, wherein a porous medium is interposed between the blood collection bag and the satellite bag, the porous medium comprising modified polybutylene terephthalate fibers having a CWST of 70 dynes/cm to 115 dynes/cm and a zeta potential of -3 to -30 millivolts at pH of 7.3, and said porous medium bars the passage of red blood cells therethrough, but permits the pas-
- 39. A filter element for processing blood comprising a porous, fibrous medium which removes leucocytes and blocks red blood cells, but which permits
  platelet-rich plasma to pass therethrough.
  - 40. The filter element of claim 39 wherein said fibrous medium has a CWST of at least 70-115 dynes/cm.
- 41. The filter element of claim 39 wherein the zeta 20 potential is -3 to -30 millivolts at pH of 7.3.
  - 42. The filter element of claim 41 wherein the zeta potential is -7 to -20 millivolts at pH of 7.3.
  - 43. The filter element of claim 42 wherein the zeta potential is -10 to -14 millivolts at pH of 7.3.
- 25 44. The filter element of claim 43 wherein the surface area of the fibers of the filter is greater than  $0.3 \text{ M}^2$ .

- 45. The filter element of claim 44 wherein the surface area is 0.3 to 2.0  ${
  m M}^2$ .
- 46. The filter element of claim 45 wherein the surface area is .35 to .6  $M^2$ .
- 5 47. The filter element of claim 46 wherein the voids volume of the filter is 71% to 83%.
  - 48. The filter element of claim 47 wherein the voids volume is 75% to 80%.
- 49. The filter element of claim 39 wherein the flow area of the filter is 2.5-10 cm<sup>2</sup>.
  - 50. The filter element of claim 49 wherein the flow area is  $3-6 \text{ cm}^2$ .
- 51. The filter element of claim 39 wherein the fibrous medium comprises polybutylene terephthalate fibers.
  - 52. A device for the collection and processing of blood comprising a blood collection bag and at least one satellite bag connected thereto, wherein a porous medium is interposed between the blood collection bag and the satellite bag the porous medium
- tion bag and the satellite bag, the porous medium comprising modified polybutylene terephthalate fibers having a CWST of 70 dynes/cm to 115 dynes/cm and a zeta potential of -3 to -30 millivolts at pH of 7.3, and said porous medium removes leucocytes
- and bars the passage of red blood cells therethrough, but permits the passage of platelets.

- 53. A method for treating whole blood comprising
  - a. centrifuging whole blood; and
- b. passing the supernatant layer of the
   centrifuged liquid through a filter until red blood
   cells block the filter.
  - 54. A method of collecting and processing blood in the device of claim 1 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 10 55. A method of collecting and processing blood in the device of claim 3 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 56. A method of collecting and processing blood in the device of claim 6 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 57. A method of collecting and processing blood in the device of claim 7 comprising passing platelet20 rich plasma from the first container through the filter to the second container.
  - 58. A method of collecting and processing blood in the device of claim 11 comprising passing plateletrich plasma from the first container through the filter to the second container.

59. A method of collecting and processing blood in the device of claim 17 comprising passing plateletrich plasma from the first container through the filter to the second container.


¥

- 60. A method of collecting and processing blood in the device of claim 18 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 5 61. A method of collecting and processing blood in the device of claim 19 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 62. A method of collecting and processing blood in the device of claim 22 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 63. A method of collecting and processing blood in the device of claim 31 comprising passing platelet15 rich plasma from the first container through the filter to the second container.
- 64. A method of collecting and processing blood in the device of claim 35 comprising passing plateletrich plasma from the first container through the filter to the second container.
  - 65. A method of collecting and processing blood in the device of claim 38 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 25 66. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 39.

67. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 40.

Ŧ

- 68. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 41.
  - 69. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 44.
- 10 70. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 47.
- 71. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 49.
  - 72. A method of collecting and processing blood comprising passing platelet-rich plasma through a filter element of claim 51.
- 73. A method of collecting and processing blood in the device of claim 52 comprising passing plateletrich plasma from the first container through the filter to the second container.
- 74. A device comprising a housing and means disposed within the housing for permitting platelets suspended in plasma to flow therethrough, but which prevents passage of red blood cells.






FIG. 2

I. GLASSIFICATION OF SUBJECT MATTER (if several classification symbols apply, indicate all) <sup>3</sup>					
According to International Patent Classification (IPC) or to both National Classification and IPC					
IPC(5): B011	IPC(5): B01D / 24/02				
II. FIELDS SEARC	<del></del>				
<u> </u>	Minimum Documer				
Classification System	11	Classification Symbols			
v.s.	604/4,5,6,405,408,410 210/435,446,503-508,651,76	67			
	Documentation Searched other to the Extent that such Documents	han Minimum Documentation are Included in the Fields Searched 6			
	CONSIDERED TO BE RELEVANT 14  altion of Document, 16 with indication, where app	consists, of the relevant passages 17	Relevant to Claim No. 16		
770	A, 4,687,580 (MALBRANC)	et al.) 18 August			
, <del></del>	•				
1987		h -1 \ 21 Year 1000			
	A, 4,747,952 (NAKANO et				
1 42	A, 4,111,199 (DJERASSI)				
A US,	A, 4,447,220 (EBERLE) (	08 May 1984	·		
A US,	A, 3,513,976 (JAMES) 20	6 May 1970			
A US,	A, 4,040,959 (BERMAN	et al.) 09 August			
1977					
us.	A, 4,663,032 (LOOS et a	al.) 05 May 1987			
A	A, 4,187,979 (CULLIS e		<u> </u>		
1980					
	A, 4,464,167 (SCHOENI	NOPEER et al.) 07			
1		DOM: DR. CC uz., or	· ·		
1 -	st 1984	' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '			
A US,	A, 4,608,178 (JOHANSSOI	N et al.) 26 August	i		
1986					
A US,	A, 4,596,657 (WISDOM)	24 June 1986			
A US,	<u>A, 4,767,541 (WISDOM)</u>	30 August 1988	<u> </u>		
<ul> <li>Special categories of cited documents: 15</li> <li>"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the</li> </ul>					
considered to be of particular relevance invention					
"E" earlier document but published on or after the international filing date "L" document which may throw doubts on priority claim(s) or involve an inventive step					
which is cited to establish the publication date of another which is cited to establish the publication date of another citation or other special reason (as specified)  "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the					
"O" document referring to an oral disclosure, use, exhibition or other means  other means					
"A" document published prior to the international filing date but later than the priority date claimed "A" document member of the same patent family					
IV. CERTIFICATION					
Date of the Actual Completion of the International Search 2  Date of Mailing of this International Search Report 2					
03 JANUARY 1990					
International Search	ning Authority 1	Signature of Authorized Officer 20	in The		
ISA/US		KEVIN G. ROONEY			

	MENTS CONSIDERED TO BE RELEVANT (CONTINUED FROM THE SECOND SHEET	n
Category *	melet de constitue de la const	Relevant to Claim No 15
	US, A, 4,330,410 (TAKENAKA et al.) 18 May 1982	
A	US, A, 4,416,777 (KURODA et al.) 22 November	
	1983	
A	US, A, 4,663,058 (WELLS et al.) 05 May 1987	
A	US, A, 4,880,548 (PALL et al.) 14 November	
	1989 US, A, 4,776,964 (SCHOENDORFER et al.) 11	
A	October 1988	·
A	US, A, 4,322,298 (PERSIDSKY) 30 March 1982	
A	US, A, 4,657,117 (NEUMANN et al.) 23 June 1987	,
A	US, A, 4,720,284 (MCCARTY) 19 January 1988	
A ·	US, A, 4,915,848 (CARMEN et al.) 10 April 1990	
Ì		
	·	
	·	

Form PCT/ISA/210 (extra sheet) (May 1986)